

A blurred, underwater photograph showing several scuba divers in a blue-toned environment. One diver in the foreground is facing away from the camera, while others are visible in the background. The water is slightly cloudy, creating a professional and somewhat mysterious atmosphere.

# K3 PEKERJAAN DALAM AIR

## PEKERJA SELAM



# PEKERJA SELAM

- Orang yang bekerja didalam air dan mendapat tekanan atmosphere lebih dari 1 atm



# BEKERJA DI DALAM AIR

- BEKERJA DIBAWAH AIR → LINGKUNGAN BERBAHAYA



# ESTIMASI RESIKO AKTIVITAS DALAM AIR

<b>Population</b>	<b>Risk</b>	<b>Source</b>	<b>Accuracy</b>
<b>Mortality</b>			
Recreational divers	1/6250 divers/yr	DAN USA <sup>2</sup>	Estimation
Sports Divers (UK)	1/5000 divers/yr	HSE/BSAC <sup>66</sup>	Estimation
Occupational Divers (UK)	1/21000 divers/yr	HSE	Fact
Occupational Divers (Alaska)	1/600 divers/yr	CDC 1989- 97 <sup>67</sup>	Fact
<b>Decompression sickness (DCS and AGE)</b>			
Military Divers (US)	1/76000 dives	Arness <sup>68</sup>	Estimation
Recreational Divers (Aus)	1/15000 dives	SPUMS <sup>69</sup>	Estimation
Recreational Divers (USA)	1/2900 dives	Bove <sup>70</sup>	Fact
Commercial Divers (USA)	1/280 dives	Bove <sup>70</sup>	Fact
Military Divers (USA)	1/3770 dives	Bove <sup>70</sup>	Fact
Recreational Divers <-30m (Europe)	1/40228 dives	DAN Europe <sup>71</sup>	Estimation
Recreational Divers (any depth) (Euro)	1/6604 dives	DAN Europe <sup>71</sup>	Estimation
Sports Divers (UK)	1/10500 dives	BSAC <sup>66</sup>	Estimation
Sports Divers (Cold Water Wrecks)	1/270 dives	DAN USA <sup>2</sup>	Fact
Dive Instructors Liveaboard	1/1000 dives	DAN USA <sup>2</sup>	Fact
Sports Divers (Cold Water)	1/1250 dives	Trevett et al. <sup>72</sup>	Fact

# KECELAKAAN KERJA



## Oil & Gas Related Offshore Diving Fatalities in the North Sea Since 1971 (21 Primary, Secondary or Contributory Causes Involved)

Nov 2007

Identified Causes	Number Related Accidents	Specific Accidents, identified by chronological ranking where each given cause was a factor
Poor / Inadequate <b>Supervision</b>	21	1-3-10-11-13-16-18-20-21-23-25-29-36-40-42-45-46-49-51-52-53
Poor / Inadequate Diver <b>Training</b>	17	2-5-7-8-10-12-13-14-16-18-20-26-28-32-34-37-44
Poor / Inadequate <b>Equipment Design</b>	17	2-5-7-8-13-21-24-28-33-36-38-39-43-46-47-50-51
Use of <b>SCUBA</b> Technique	15	1-4-6-9-12-17-18-19-22-26-27-29-30-32-41
Diver or Diver Equipment <b>Entanglement</b>	14	2-3-13-14-25-29-34-37-39-40-44-47-51-53
Poor Worksite <b>Management</b> or <b>Organisation</b>	13	15-35-36-39-40-42-45-46-49-50-51-52-53
Poor / Inadequate <b>Communication</b> or <b>Cover up</b>	12	12-13-15-16-18-23-30-36-43-49-50-52
<b>Traumatic Injury</b> other than Asphyxia or Drowning	12	12-15-24-35-42-43-46-47-48-49-50-52
Poor / Incompetent <b>Rescue</b>	7	1-8-20-32-46-48-51
Poor <b>Launching System</b> or Procedure	6	1-24-29-30-42-47
Diver <b>Over-Exertion</b>	6	4-8-16-17-31-48
<b>Wrong Gas</b> Supplied to Diver	5	11-16-23-36-45
<b>Dynamic Positioning</b>	4	37-40-42-49
<b>Mismanagement of Change</b>	4	7-24-25-52
<b>Bad Weather</b> Conditions	4	14-25-29-37
Unappreciated <b>Differential Pressure</b>	3	5-15-19
Poor / Incompetent <b>Medical Management</b> / Treatment	3	3-10-45
Pre-Existing Undetected <b>Medical Condition</b>	3	9-17-48
<b>Transfer Under Pressure</b> Failure or Inadverted Operation	2	21-43
<b>Hypothermia</b>	2	1-16
<b>Hyperthermia</b>	1	21


# STANDART

- KOMPETENSI PENYELAM
- PERALATAN YANG DIPAKAI
- INSTALASI ALAT YANG DIPERGUNAKAN
- PROSEDUR OPERASI PENYELAMAN



# PENGAKUAN KOMPETENSI

- Diri sendiri
- Perusahaan
- Nasional
- Internasional



# **KLASIFIKASI KOMPETENSI**

KEPUTUSAN DIREKTUR JENDERAL PEMBINAAN PENGAWASAN KETENAGAKERJAAN  
NO. KEP. 64 / PPK / XI / 2013

- PEKERJA SELAM KELAS 1 / COMMERCIAL SCUBA
- PEKERJA SELAM KELAS 2 / SSBA DIVER
- PEKERJA SELAM KELAS 3 / SATURATION DIVER



# CONTOH PERALATAN



- SCUBA




- SSBA



# CONTOH INSTALASI PERALATAN



# contoh management underwater ship husbandry operation



A large cargo ship with a dark hull and white superstructure is sailing on a calm sea under a clear blue sky.

**BE PREPARE  
BE SAFE**